

# Environmental assessments

We have undertaken a wide range of environmental surveys and technical assessments to understand existing site conditions. These have informed mitigation measures and will support our planning application to Perth and Kinross Council.

# Surveys and assessments include:





# Landscape and visual

### ASSESSMENT STATUS

The full assessment is underway.

Baseline photography and photomontages have recorded existing landscape conditions.

### MITIGATION MEASURES IN DESIGN

- Planting of native species on the northern edge to screen solar panels.
- Retention of local landscape features with added scrub planting at the southern corners.

# Archaeology and cultural heritage

#### **ASSESSMENT STATUS**

A walkover survey found no previously unrecorded assets.

Impacts on the setting of heritage assets, including Balvaird Castle and a nearby potential prehistoric hillfort, are being assessed.

A historic environment desk-based assessment will support the application.

### MITIGATION MEASURES IN DESIGN

- Low potential for unrecorded archaeology across most of the site, moderate potential in the east near the hillfort.
- We'll agree mitigation with Perth and Kinross Council and Perth and Kinross Heritage Trust.

# Hydrology

# ASSESSMENT STATUS

Walkover surveys confirmed the location of watercourses and private water supplies.

A Sustainable Drainage System (SuDS), flood risk assessment, and drainage strategy are being prepared.

# MITIGATION MEASURES IN DESIGN

- Minimum 50m buffer from watercourses for the BESS, 10m for solar panels.
- Drainage design includes a detention basin to manage runoff and retain pollutants in the event of a fire.
- Buffers maintained around private water supplies.

# Transport

# ASSESSMENT STATUS

Access arrangements have been assessed. Traffic surveys will inform a Transport Statement and Construction Traffic Management Plan.

# MITIGATION MEASURES IN DESIGN

- Access from the A912 with an agreed visibility splay.
- The Construction Traffic Management Plan will control delivery times, wheel cleaning, dust and noise.

If you have any comments or questions about any aspect of the project please talk to a member of the project team or visit our website.



